

**SECTION 014339 - MOCKUPS**

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Integrated exterior mockups.
2. Integrated Interior mockups.

1.2 DEFINITIONS

A. Integrated Exterior Mockups: Mockups of the exterior envelope constructed on-site as freestanding temporary built elements consisting of multiple products, assemblies, and subassemblies.

1. Terra Cotta Rainscreen system integrated w/ Curtainwall system – one story in height (2) bays of terra cotta, with single curtainwall bay intersection
2. Composite Metal Panel one story in height and approximately 9'-0 in width to capture intersection of window system, metal panels of varied depths and break metal brow at floor line. (Similar to Detail 5/A-321A)
3. 4'-0" x 4'-0" demonstrating the use of form liner for wood look at exterior concrete walls.
4. 4'-0" x 11'-0 wide section of mural wall assembly. (Reference Detail 6/A-538 and Graphic Dwg A-1000)

B. Integrated Interior Mockups: Mockups of prime interior spaces as freestanding temporary built elements consisting of multiple products, assemblies, and subassemblies for the following areas:

C. 1. Public lobby millwork elements for both buildings

1.3 PREINSTALLATION MEETINGS

A. Preinstallation Conference: Conduct conference at project site.

1.4 QUALITY ASSURANCE

END OF SECTION 014339